



NOTES:

1. EXPANSION JOINTS OF 3/16" CELLULOSE OR SIMILAR APPROVED MATERIAL SHALL BE PLACED AT 10' INTERVALS.
2. CONTRACTION JOINTS 1" DEEP HAVING 1/4" RADIUS EDGES SHALL BE PLACED AT 5'-0" INTERVALS IN SIDEWALK.
3. EDGES SHALL HAVE 1/2" RADIUS.
4. USE 3000 PSI CONCRETE.
5. BROOM FINISH TOP SURFACE.

SIDEWALK DETAIL

SCALE: NTS



Farr Engineering

PO BOX 302 PORT JERVIS, NY 12771
914-474-1980

CITY OF PORT JERVIS
ORANGE COUNTY, NEW YORK

SIDEWALK DETAIL